

PROJECT SCOPE
For
City of Medina Job No. 1185: 2025 Concrete Street Repair Program

General

This Project consists of removal and replacement of existing concrete pavement within the City of Medina. The existing pavement sections to be removed are typically plain concrete pavement, typically between six (6) inches to ten (10) inches thick without any base material. The new pavement to be placed will be between eight (8) and twelve (12) inches of reinforced concrete pavement and will include the addition of two (2) of aggregate subbase. As such, excavation and removal of subgrade soils is included within the project. In certain sections this project will include the installation and connection of four (4) inch curb drains along the pavement edges.

The City utilizes four (4) types of concrete pavement, RESIDENTIAL pavement, COLLECTOR pavement, HEAVY DUTY pavement and INDUSTRIAL-THOROUGHFARE pavement. Information about the design standards for these pavement types is included within the CONTRACT SPECIFICATIONS section.

For this project, the Contractor will be required to provide all four pavement types at the various locations indicated. The Contractor will be required to supply Type MS concrete for all pavement types. These requirements are outlined within the bid documents.

Maintenance of Traffic (MOT) is a unit price bid item. Please note, in addition to the MOT, portable traffic signals and Law Enforcement Officers (LEOs) are also unit price items. Reference Section 5b: Special Conditions for details as to where portable traffic signals and LEOs shall be used. The City shall set the unit price bid amount for LEOs; it will be reflected in the bid form. Please note, utilizing LEOs on site does not relieve the contractor of the responsibility to provide flaggers when required.

Bid Information

The Bid includes the following:

- Partial width removal and replacement of approximately 5767 square yards of isolated pavement sections at seventy-three (73) various locations within the City of Medina. The locations of these areas are included within both the Contract Plans and the Specifications section of these Construction Documents. Please note, these isolated sections are not concentrated at any one area, they are distributed across the entire City.
- For a bid to be considered for award, the following items must be submitted:
 1. Non-Collusion Affidavit (included within Section #8 of the bid documents)
 2. Bidder Information and Experience Record (included within Section #8 of the bid documents).
 3. A certified check or cashier's check, or bid bond in the amount of ten percent (10%) of the amount bid (supplied by the Bidder)
 4. Bid Proposal (included within Section #8 of the bid documents).

Bid and Award Date

Bids will be accepted until 10:00 A.M. on Wednesday, July 2, 2025 at which time they will be opened and read publicly. A voluntary pre-bid meeting will be conducted at 10:00 AM on Wednesday, June 25, 2025 at Medina City Hall, 132 N. Elmwood Avenue, Medina, Ohio. Contractors shall assume that the City will award the bid by Monday, July 14, 2025. The City anticipates issuing a notice to proceed no later than Friday, July 18, 2025. The City of Medina reserves the right to reject any and all bids and to waive any informalities or irregularities in the bid.

The City of Medina reserves the right to reject any and all bids and to waive any informalities or irregularities in the bid.

Completion Date

This project must be completed no later than November 30, 2025. Within the bid form, Contractors who so choose may submit a completion earlier than November 30, 2025. Bids with proposed completion dates beyond November 15, 2024 WILL NOT BE CONSIDERED FOR AWARD. Please note, completion date will be a factor during the review and consideration of the bids received. It is possible that a bid other than the lowest bid received may be selected due to a more favorable completion date